ATTACHMENT 4 SECURITY PLAN

Security Plan

1.0 Security Control

Security is of paramount importance to the safe and successful operation of the TTU. Security measures taken to control entry and prevent mishap are incorporated to ensure that (1) the public or grazing livestock are prohibited access to the TTU and (2) Oasis and HAFB support personnel are protected from the potential safety and health hazards associated with TTU operations.

1.1 Fences and Natural Barriers [40 CFR 264.14(b)(2)(i) and UAC R315-8-2.5(b)(2)(i)]

Access to the TTU is controlled by means of three- and four-strand wire fences, cliffs, and mountainous terrain (see Figures 2 and 3 of Attachment 1). These barriers not only restrict public entry, but also deter trespass by grazing livestock animals.

1.2 Warning Signs [40 CFR 264.14(c) and UAC R315-8-2.5(c)]

Located on the gates, and every 91 meters (300 ft) along the perimeter fence, are posted signs indicating, Danger \Box Explosive Disposal Range \Box Keep Out. Since English is the predominant language in the area surrounding the TTU, multilingual signs are not required.

2.0 Entry Control [40 CFR 264.14(b)(2)(ii) and UAC R315-8-2.5(b)(2)(ii)]

Entry to the TTU is gained through any one of seven gates surrounding the facility (see Figure 3 of Attachment 1). These gates are locked except when TTU access is required. Lock combinations are on file in the Main HQ building, the Civil Engineer Control Room, and the Security Police Office.

Oasis Security Police patrol the TTU once each day to deter unauthorized access. They observe the entire TTU for fence integrity, security of the entrance gate, signs of any unauthorized entry, and/or the presence of any unauthorized vehicles. Should intruders be detected, the Security Police will apprehend them and either escort them off the facility or turn them over to civil authorities, as required. Patrols are in constant radio contact with the Security Police dispatcher in Oasis.

For TTU operations whose Q-D calculations indicate the potential for fragments reaching or extending beyond Box Elder County Road, the road will be blocked north and south of the TTU. This prevents anyone from inadvertently being hit by high-speed fragments. Security Police stand by at the Oasis compound for all operations. In case of an intruder, TTU operational personnel would stop their operations and summon the Security Police via either radio or cellular telephone.

Controlling entry into the TTU during OB/OD operations is the responsibility of the RSO¹.

¹An RSO is a qualified EOD team member specifically designated to oversee all safety—as opposed to operational—aspects of the TTU operation. The operations team chief and RSO are never the same person.

3.0 Fire Breaks

Firebreaks (a minimum of 15 ft wide) follow the perimeter and crisscross the TTU as shown in Figure 2, Attachment 1. They are maintained annually. Firebreaks also serve as emergency egress routes for personnel operating any of the TTU Sites.